2023 PRODUCT PRICE LIST

ADDITIONAL CHARGES	Extra per m3
Environmental Compliance Fee	\$5.00
Chute Wash	\$5.00
Polypropylene Fibers (0.9kg/m3)	\$20.00
Superplasticizer Mid (slump 120+/- 30mm)	\$15.00
Superplasticizer High (slump 150+/- 30mm)	\$18.00
Pump Mix (20MPa to 25MPa)	\$12.00
Calcium Chloride- 1%	\$9.00
Calcium Chloride- 2%	\$12.00
Silica Fume (Min. 48 hrs notice)	On Request
Air Entrainment	On Request
TOARC & Carbon Tax	\$2.50
Winter Handling (Nov 1st-April 30th)	\$20.00
Corrosion Inhibitor	\$4.50/litre
Cooling	On Request
Crystaline Concrete Waterproofing	On Request
Return concrete 2m3 or greater	\$25.00 m3

POUR CANCELLATION FEE:

A minimum charge of \$1,000 per order will be applied to all same day pour cancellations. This charge will help to cover the costs for the first truck, batcher and loader operator. For each additional truck booked, an additional \$250 charge will be applied. Notice of cancellation must be received by 4pm the day prior to delivery. Weekend and Monday deliveries will require notice by 4pm Friday.

MINIMUM LOAD CHARGE:	Extra per load
Less than 7m3 Less than 6m3 Less than 5m3 Less than 4m3 Less than 3m3 1 balance load per order (7m3 min order)	\$50.00 \$100.00 \$150.00 \$200.00 \$250.00 No Charge
FUEL SURCHARGE:	Extra per m3
* Flex fuel - Adjusted monthly - Ask for chart	\$5.00 \$m3

SEASONAL LOAD RESTRICTION CHARGE:	Extra per load
When MTO reduced load limits are in effect	\$400.00

HOT AND COLD WEATHER CONCRETE RECOMMENDATIONS

When placing, finishing and curing concrete at temperatures below 5C and above 27C, we strongly recommend that you consult the current CSA A23.1 specification. This specification details the measures that must be taken to ensure a high quality finished product.

Leaders In Modernizing Concrete

Viola Ready Mix is founded on expertise that has been developed over four decades, new technology in the modernizing of the Ready Mix Industry, professional, dependable customer service and a strong commitment to safety. Strategically located in Markham, our flagship plant is positioned to be the largest concrete batching plant in Canada. This state-of-the-art mixing plant caters to municipalities, businesses, and individual residential/ commercial property owners or developers. It was designed to meet and exceed the growing concrete demand and delivery challenges of the GTA from a small project to large superstructures.

Pride in every pour: Exceeding our customers' expectations is our reward. We strive to be the supplier of choice in our industry and the standard setter in quality and productivity providing exceptional customer service.

MARKHAM LOCATION UNDER CONSTRUCTION

- © 500+ m3/hour
- Q 2 Wet + 1 Dry batching capabilities
- Simultaneous loading
- Complete back up Plant redundancy



READY MIX INC

LOCATIONS:

Markham: 2815 14th Ave North York: 87 Fenmar Dr. Brampton: 10 Cadetta Rd. Scarborough: Coming Soon

2815 14th Avenue, Markham, Ontario L3R 0H9 • Dispatch | 905.475.7765 • violareadymix.com VIOLA ALLIANCE GROUP READY MIX | ASHPHALT | PAVING | CONSTRUCTION | LABS | SOFT SCAPE | WINTER SERVICES

VI OLA READY MIX INC.

2023 PRODUCT PRICE LIST violareadymix.com





2023 PRODUCT PRICE LIST

STRENGTH MIXES (110mm Slump Max, 20mm Aggregate)

10 MPa	\$215.00 m3	35 MPa	\$267.00 m3
15 MPa	\$221.00 m3	40 MPa	\$275.00 m3
20 MPa	\$229.00 m3	45 MPa	\$325.00 m3
25 MPa	\$246.00 m3	50 MPa*	\$365.00 m3
30 M Pa	\$254.00 m3	55 MPa*	\$385.00 m3

*150 +/- 30mm slump achieved through use of high range water reducer – Higher strengths available upon request

RESIDENTIAL MIXES (Air Entrainment Included)

15 MPa	OBC 0.70 w/cm ratio wall mix	180mm slump max	\$235.00 m3
201402	OBC 0.70 w/cm ratio wall mix	180mm slump max	
	7		
25 MPa	OBC 0.65 w/cm ratio 20mm Agg.	110mm slump max	\$244.00 m3
32 MPa	C2 0.45 w/cm ratio 20mm Agg.	110mm slump max	\$272.00 m3

0.55 w/cm

INDUSTRIAL FLOOR MIX (180mm Slump Max)

CSA SPECIFICATION MIXES (110mm Slump Max, 20 mm Aggregate)

Strength	Class of exposure*	W/CM Ratio	Price
25 MPa	F-2, C-4	0.55	\$255.00 m3
30 MPa	F-1, C-3, S-3	0.50	\$263.00 m3
32 MPa	C-2, S-3	0.45	\$272.00 m3
35 MPa	C-1, S-1	0.40 <1500 coulombs	\$280.00 m3
40 MPa	C-1	0.40 <1500 coulombs	\$300.00 m3
45 MPa	C-1	0.40 <1500 coulombs	\$338.00 m3
50 MPa*	CXL	0.40 <1000 coulombs	\$375.00 m3

*150 +/- 30mm slump achieved through use of high range water reducer --Higher strengths available upon request

GROUT MIXES

1:4	10 MPa	\$290.00 m3	1:2	25 MPa	\$325.00 m3
1:3	15 MPa	\$305.00 m3	1:1.5	30 MPa	\$350.00 m3
1:2.5	20 MPa	\$314.00 m3	1:1	35 MPa	\$370.00 m3

CAISSON & SHORING MIXES (180mm Slump Max)

0.4 MPa	Piling Mix (grout) \$204.00 m3	20 MPa	Caisson	\$245.00 m3
2 MPa	Piling Mix (grout) \$205.00 m3	25 MPa	Caisson	\$253.00 m3
4 MPa	Piling Mix (grout) \$206.00 m3	30 MPa	Caisson	\$264.00 m3
5 MPa	Piling Mix (grout) \$206.00 m3	35 MPa	Caisson	\$275.00 m3

CONTROLLED DENSITY FILL MIXES (110mm Slump Max)

0.4 MPa Unshrinkable Fill (Metro Toronto Spec) 180mm Slump Max	\$209.00 m3
0.7 MPa Unshrinkable Fill (180mm Slump Max)	\$210.00 m3
0.4 / 0.7 MPa SUPER FLOW (250 mm Slump Max)	\$230.00 m3
4.0 MPa	\$214.00 m3
7.0 MPA	\$219.00 m3
8.3 MPa (10mm agg included)	\$233.00 m3

HIGH PERFORMANCE CONCRETE - SCC (Self Consolidating Concrete) Price per m3

*Concrete that will spread, flow and consolidate under its own weight.

*Super Flow SCC	600mm+ Flow	Specify Strength	Upon request
Semi Flow	190mm-250mm Slump Max	Specify Strength	Upon request

SERVICES AND DELIVERY

REGULAR HOURS:

Monday through Friday, 7:00)am to 5:00pm
For completion of deliveries	started between
7:00am and 5:00pm	
After 5:00pm and before 9:0	0pm Add \$35.00/m3
After 9:00pm and before 7:0	0am
(+ Plant Opening fee)	Add \$50.00/m3
PLANT OPENING FEES:	
Plant	\$5,000.00

Order Cancellation \$1,000.00

SATURDAY DELIVERY:

From April 1st-November 30th \$30.00/m3 (7am-1pm) Minimum Combined Volume of 75m3 required to open plant. For other than above see Plant Opening fees.

DELIVERY:

\$260.00 m3

Due to the number of variables outside of Viola's control including but not limited to traffic, weather and power failures, Viola offers it's services on a best effort basis. While we have the capacity to serve the express needs, Viola cannot guarantee delivery rates and schedule beyond what would be reasonably within it's control. Furthermore, pricing is offered with the explicit understanding that Viola will not accept any backcharges related to perceived service failures or delays. Safe and adequate staging for ready mix trucks is required on sites. Viola will work with the contractor to determine the required staging space, truck turning radius requirements, safe washout areas, site entry and exit logistics and safety

HIGH EARLY STRENGTHS Accelerated Strength Mixes

(Includes slump of 150mm +/- 30mm slump)

75% Design			
Strength in	24H	48H	72H
20 MPa	\$50.00 m3	\$42.00 m3	\$36.00 m3
25 MPa	\$52.00 m3	\$46.00 m3	\$38.00 m3
30 MPa	\$54.00 m3	\$46.00 m3	\$40.00 m3
32 MPa	\$55.00 m3	\$49.00 m3	\$42.00 m3
35 MPa	\$58.00 m3	\$52.00 m3	\$44.00 m3
40 MPa	\$62.00 m3	\$54.00 m3	\$46.00 m3
45 MPa	\$65.00 m3	\$54.00 m3	\$49.00 m3
50 MPa	\$72.00 m3	\$60.00 m3	\$50.00 m3

To achieve 75% of 28 day strength based on Minimum Temperature of 20C

Curing Environment as per CSA Requirements

considerations for drivers and the public. The ultimate responsibility to provide trained flagmen and staging areas will reside with the contractors.

DEMURRAGE:

60 minutes per load will be allowed to unload		
Every minute in excess of 60 min.	\$10.00/minute	
COLOUR:		

Coloured Concrete	Upon Request
Truck wash fee on colour loads	\$100.00/load
Red Colour for conduits	\$40.00/m3

QUALITY ASSURANCE & SITE SUPERVISION:

Cylinder testing on request	
(4 cylinders)	On Request
Site supervision	
(on customer's request)	On Request

QUALITY NOTE:

Quality Control is of utmost importance to Viola. Viola products are designed to be used as delivered. Unauthorized additives or alterations to the product, or any other improper use, can adversely impact product quality. To ensure product quality, additions and alterations are expressly prohibited, and will void any actual or implied warranties. For specialty concrete products, the minimum load size is 3m3 to ensure batching accuracy. Concrete guarantees include slump (off the chute), temp., air range, and 28 day strengths as per CSA. Viola Ready Mix shall not accept any claims regarding "surface acceptance" if the above criteria has met CSA requirements.

POLAR PRODUCTS - COLD WEATHER ADDITIVE			a	
PRODUCT	LEVEL	RANGE	PRICE	Т
PolarMix 1	Level 1	10c to 7c	\$30.00 m3	
PolarMix 2	Level 2	6c to 3c	\$35.00 m3	lı fo
PolarMix 3	Level 3	2c to-1c	\$42.00 m3	
PolarMix 4	Level 4	-2c to-5c	\$53.00 m3	o S
PolarMix 5	Level 5	-6c to-10c	\$59.00 m3	ir
Temp Range ind	cludes the ami	bient Temperatur	e 12 hours	

after pouring. Check your local weather forecast.



SET

Туре Туре

LIG

Type Sem Ligh Full

Nov SPE

Air \ Line Rapi Mod





3m3 Minimum required to ensure a quality product on all strengths including any High Early Mixes.

TAXES

TERMS

Invoices are due for payment in full no later than the last business day of month following Invoice. Interest at 1.5% monthly (18% per annum) will be charged on overdue accounts. Prices are firm only if covered by a written quotation and are subject to terms and conditions thereon. All pricing is subject to a min \$10.00 m3 increase January 1st.

Leaders In Modernizing Concrete

CIAL AGGREGATES		
- 14 mm Stone mm Stone		\$ 20.00 m3 Upon request
RETARDING ADMIXTURES		
e R (2 hours) e RX (4 hours)		\$ 12.00 m3 \$ 18.00 m3
HTWEIGHT CONCRETE MIXES		
be ni Light Weight nt Weight I Light Weight <i>vember 1st to April 30th addi</i>	Target Density 2,000 kg/m3 Dry Weight 1,840 kg/m3 Dry Weight 1,600 kg/m3 <i>tional \$50 m3 – water dousing</i>	Price Upon Request Upon Request Upon Request
CIFICATION TESTING CHARGES	5	
Void System Analysis ear Shrinkage Test oid Chloride Permeability ock Up Samples or Trials		\$1600.00 / test \$2100.00 / test \$1600.00 / test \$1500.00 / trial

Charges will apply for each mix test required. Customer responsible for cost of load (s)

\$100.00 m3

\$145.00 m3

Upon Request

COOLING CHARGES

Specified Max Temp 26 – 30 Celsius (ice) Specified Max Temp 22 - 25 Celsius (ice) Under 22 Celsius (using liquid nitrogen)

QUALITY NOTE

Applicable HST will be added. Any Legislated tax increases on materials will be also applied prior to completion of projects.

